GOOD MORNING....

Welcome to the Asset Management Program Informational Meeting #2

The presentation will begin shortly.





Agenda

- Introductions
- Review of 1st public meeting
- St. Joseph's asset management progress
- Project Priority List (PPL)
- Next Steps





Introductions

Engineering Personnel

- Tim Zebell, City Engineer
- Alex Austin, Assistant City Engineer

Public Services Personnel

- Greg Grothous, Director of Public Works
- David Linderman, Deputy Director of Public Works
- Liam Cormier, Superintendent, Streets and Sanitation

Asset Management Consultants

- Shawn Keough, Wade Trim
- David Delia, Wade Trim
- Tim Drews, Abonmarche



Sustainability Committee Members

- Mayor Laura Goos
- Kim Jorgensen Gane
- Paul Gillespie
- Larry O'Brian
- Lisa VanBladeren
- Chris Lannert
- Jill Plescher



Purpose of Public Meetings

Meeting #1

What we are planning

- SAW Grant Overview
- Introduction to Asset Management
- Draft AM Policy



Meeting #2

What we are doing

Communicate
 Progress

- Risk Register
- Draft PPL

Meeting #3

What we have done

Review

- Progress/Deliverables
- Final Policy
- CIP Discussion
- Long Term Planning
- What's next

What is Asset Management?

"Asset management is the practice of managing infrastructure capital assets to minimize the total cost of owning and operating these assets while delivering the desired service levels"

- USEPA

- Risk Management
- Good Stewardship
- Continuous Improvement Process






Asset Management Program Currently Includes

AMP currently focuses on infrastructure in the right-of-way

- Streets & storm sewers
- Water distribution system
- Sanitary sewer collection system including Lift Stations
- The goal is to expand program to other City assets over time.








Progress

- MIC Assessment Management Readiness Scale
- AM Policy
- Strategic AM Plan (Draft)
- AM Plan Update (Draft)
- Risk Register
- Draft Project Priority List



Asset Management Policy

- Sustainability Committee recommended approval July 12, 2022
- City Commission adopted on July 25, 2022
- Establishes principles that guide decisions
 - 6 Objectives
 - 4 Principles
 - 6 Policy Statements







Draft Strategic AM Plan (SAMP)

- Describes the AM Program
- How St.
 Joseph will meet the objectives in the AM Policy








Draft AM Plan

- Documents the risk-based methodology for achieving AM objectives
- Documents the current risk and future plans



Risk = Consequence of Failure X Likelihood of Failure


Asset Management Plan Results







Asset Management and the CIP



Data Driven Decisions (the Risk Register)

Asset Types Included Now

- Sanitary Gravity Mains
- Sanitary Manholes
- Combined Manholes
- Sanitary Pressurized Mains
- Sanitary Lift Stations

- Paved Streets
- Storm Gravity Main
- Water Mains
- Water Laterals*

* Included independently from risk registers





Expanding the AM Program

Asset Types to be included in the Future

- Valves
- Hydrants
- Storm Sewers
- Catch Basins
- Drains
- Detention Structures


- Clean Outs
- Signage
- Bridges
- Water Tower
- Parks
- Trees

- Parking
- Streetlights
- Signage
- Non-motorized Paths
- Sidewalks






Watermain Risk Summary



Approximately:
59 miles of watermain
64% of the system is ≥ 60 years old
37% over 100 years old or age is unknown


Sanitary Risk Summary





Approximately: 48 miles of gravity sanitary sewer 66% of the system is ≥ 60 years old 32% over 100 years old or age is unknown

Streets Risk Summary








Initial Results of the Data Driven AM Program - <u>Watermain</u>

Consequence of Failure X Likelihood of Failure






Initial Results of the Data Driven AM Program - <u>Sanitary</u>

Consequence of Failure X Likelihood of Failure







Initial Results of the Data Driven AM Program - <u>Streets</u>

Consequence of Failure X Likelihood of Failure =





Balancing Priorities







Projects Completed Since 2017 CIP

| | | SEWER | ** | Year | 2017 CIP? | Project Description |
|---|---|-------|---------|---------|--------------|--|
| | | Х | | 2018 | Yes | Telemetry at Lift Stations |
| Х | Х | Х | Х | 2018 | Yes | Wallace Avenue Reconstruction |
| | | | Х | 2018 | Yes | 2018 Sidewalk & Spot Concrete Replacement |
| | | Х | | 2019 | No | Central Ravine Interceptor I & I Removal (2017-20 HLL) |
| | | Х | | 2019 | Yes | Slip Lining |
| | | | Х | 2019 | Yes | Cape Seal |
| | | | Х | 2019 | Yes | Crack Seal |
| | | | Х | 2019 | Yes | Fog Seal |
| Х | | | | 2020 | No | 2020 High Sample LSLR (2018 LCR) |
| Х | | | | 2020 | Yes | Cut & Cap 10-inch Marina Island to Benton Harbor |
| | | HL | L = Hic | gh Lake | Level | LCR = Lead Copper Rule |

Projects Completed Since 2017 CIP (continued)

| | | SEWER | * | Year | 2017 CIP? | Project Description |
|---|---|-------|----------|------|--------------|---|
| Х | Х | Х | Х | 2020 | Yes | Orchard Ave Reconstruction |
| Х | Х | Х | Х | 2020 | Yes | Kingsley Ave Reconstruction |
| Х | Х | Х | Х | 2020 | Yes | Morton Ave Reconstruction |
| | | | Х | 2020 | Yes | 2020 Sidewalk Replacement Project |
| Х | | | | 2021 | No | Broad Street LSLR (2018 LCR) |
| | | | Х | 2021 | Yes | Concrete Pavement Prevetive Maintenance |
| Х | Х | Х | Х | 2021 | Yes | Langley Ave Reconstruction |
| Х | | | | 2022 | No | Botham Ave LSLR (2018 LCR) |
| Х | | | | 2022 | No | 2022 High Sample LSLR (2018 LCR) |
| | | | Х | 2022 | Yes | 2022 Sidewalk Replacement |

LCR = Lead Copper Rule

Projects Underway or Ongoing

| | | SEWER | *** | Year | 2017 CIP? | Project Description |
|---|---|-------|-----|------|--------------|--|
| Х | | | | 2022 | No | 2022 LSLR – Future Project Areas (2018 LCR) |
| | | Х | | 2022 | No | Inflow & Infiltration Removal Pilot |
| Х | Х | Х | Х | 2022 | Yes | Lester Ave Reconstruction |
| Х | Х | Х | Х | 2022 | Yes | Willa Drive Reconstruction |
| Х | Х | Х | Х | 2022 | Yes | Donna Drive Project |
| | | | Х | 2022 | Yes | Broad Street/Langley Avenue Resurfacing (TIP) |
| | | Х | | 2025 | Yes | CSO Project - CSO storage (Schedule Δ) |
| | | Х | | N/A | Yes | CSO Compliance |

TIP = Transportation Improvement Plan

LCR = Lead Copper Rule



Progress has been very good

- 20 Projects Completed
- 8 More Underway or Ongoing

Regulatory requirements given high priority





Upcoming Projects

Regulatory/Recurring

- Lead Service Line Replacement Project next 20 years
- CSO Compliance Program 2025 to 2027 CSO Storage
- Preventive Maintenance

Funded* Reconstruction/Rehabilitation Projects

- 2023/2024 Upton Drive Reconstruction (multiple funding sources*)
- 2024 Lake Blvd Resurfacing (TIP STUL)
- 2025 Botham Avenue Reconstruction (TIP STUL)
- 2027 Main Street/Ship Street/Port Street Reconstruction (MDOT*)





Upcoming Projects

Unscheduled Projects at the top of the priority list

- Anchors Way & Anchors Court Pavement Rehabilitation
- Anchors Way Drainage Improvements
- State Street Sanitary Sewer Retirement
- Harrison Avenue Area Sewer Replacement (Wayne & Jones)
- S State Street Resurfacing Main to Winchester
- Alco & North Pier Lift Station Rehabilitation/Replacement Funding sources come into play in the timing of these future projects.





Next Steps

- Update the CIP project priority list (PPL) with public input by October 31st
- Finalize the PPL after input, project costs, and rate study
- Future: Public Meeting #3 to present finalized CIP with rate impacts
- Utilize the CIP in the budget process; first study session in December





Asset Management Program Informational Meeting #2

Thank you for attending today!



