

### St. Joseph CSO Compliance Program - Agenda

- 1. System Overview
- 2. What is a Combined Sewer Overflow (CSO)
- 3. Why do we need to address CSO control at this time
- 4. Preliminary screening of storage options
- 5. Feasible options evaluated
- 6. Early action project
- 7. Overall project schedule
- 8. Project cost summary
- 9. Pursuing matching funding from the State of Michigan




### St. Joseph Sewer System Overview

- 1. Collection system sewers
- Combined sewer overflows (CSO)
- 3. Waste Water Treatment Plant (WWTP)




### What is a Combined Sewer Overflow?



### **Combined Sewer Overflow Control**

#### **Construction of Storage Basin**






## Why is CSO Control Being Addressed at this Time?

- 1. CSO control is mandated by the State of Michigan (EGLE)
- 2. St. Joseph has been working toward CSO control for over 20-years
  - a. Improvements have included
    - Sewer separation of combined sewers areas
    - Sewer rehabilitation in areas with high infiltration and inflow
    - Implementation of flow and rainfall monitoring program
    - Development of a computer model of the system
  - b. Final stage of CSO control is construction of a storage basin
    - Storage basin will intercept flow prior to discharge to river
    - Post event, captured flow will be dewatered back to the interceptor for treatment at the WWTP
    - Flow optimization toward the WWTP will be incorporated into design



### **Preliminary Review of Basin Storage Options**



### Preliminary Storage Basin Options – Below Grade Tank

#### <u>Pros</u>


- 1. Less visual impact
- 2. Portion of footprint can be used for other activities
- 3. Gravity dewatering

#### <u>Cons</u>

1. Higher construction cost

#### <u>Outcome</u>

1. Option was carried forward for preliminary design



### Preliminary Storage Basin Options Above Grade Circular Tank

#### <u>Pros</u>


1. Lower construction cost

#### <u>Cons</u>

1. More visible

### <u>Outcome</u>

1. Option was carried forward for preliminary design



## Preliminary Storage Basin Options – Deep Shaft

#### <u>Pros</u>


- 1. Small footprint
- 2. Less visual impact
- 3. Portion of footprint can be used for other activities

### <u>Cons</u>

- 1. Higher construction cost
- 2. Riskier construction
- 3. Higher operating cost

#### <u>Outcome</u>

1. Option not carried forward



# Preliminary Storage Basin Options – Linear Storage (Large Storage Pipes)

#### <u>Pros</u>

- 1. Less visual impact
- 2. Portion of footprint can be used for other activities

#### <u>Cons</u>

- 1. Higher construction cost
- 2. Larger area of disruption during construction
- 3. More impact with local utilities

#### <u>Outcome</u>

1. Option not carried forward



### Preliminary Storage Basin Options Rectangular Tank in Hillside

#### <u>Pros</u>

1. Reduced visual impact

#### <u>Cons</u>

- 1. Higher construction cost
- 2. Risky construction

#### <u>Outcome</u>

1. Option not carried forward



### **Evaluation of Feasible Options – Basin Siting**

- 1. Preliminary screening of potential options identified the following storage options as a good fit for the St. Joseph system
  - a. Below ground storage tank
  - b. Above ground circular storage tank
- 2. Using these options, three site locations were identified
  - a. DPW yard on Broad Street
  - b. North end of Kiwanis Park
  - c. South end of Kiwanis Park



### **Evaluation of Feasible Options – Basin Siting**

Above ground circular tank within DPW yard

Above ground circular tank at South end of Kiwanis Park

Rectangular below grade tank under box factory parking lot

Rectangular below grade tank at North end of Kiwanis Park



### **Diversion Chamber and Pump Station**

- 1. The optimal location for diversion to the basin storage is at the existing CSO-005 diversion chamber
- 2. This location intercepts all flow from the CSO-005 district and minimizes the size of the required storage basin
- 3. From this location, flow can be pumped to any of the storage site locations




### **Diversion Chamber and Pump Station Locations**


- Pump station is located away from parking lot out of floodplain
- All infrastructure in parking lot can be flush with ground surface
- No interference with parking lot



### **Diversion Chamber Configuration**



### **DPW Inlet and Outlet Sewers**




### **Kiwanis Park Inlet and Outlet Sewer Routes**

Rectangular below grade tank at North end of Kiwanis Park

Above ground circular tank at South end of Kiwanis Park

> WADE TRIM

### **Diversion Chamber and Pump Station Configurations**




### **Geotechnical Considerations**


- 1. Site specific soil bores taken at Kiwanis Park site
- 2. Historical soil bores available at low end of DPW site
- 3. Additional soil bores were collected at DPW basin and pump station locations
- 4. Based on soil bore information at DPW, tanks will require
  - Deeper pile supports
  - More robust support of excavation to control groundwater during construction



### **Geotech Considerations at DPW site**



### **Geotech Considerations at DPW site**



#### LEGEND



APPROXIMATE BORING LOCATION (SME PROJECT NO 075169.01)


Recent BOING LOCATION (PROPOSED BORING DEPTH)

NOTES: BORING LOCATIONS AND DEPTHS SUBJECT TO CHANGE DEPENDING ON FINAL DESIGN AND ENCOUNTERED SOIL CONDITIONS.



### Cost Estimate – Cost Comparison (current June 2023)

Location	DPW Site Option A	DPW Site Option B	Kiwanis Park Option C	Kiwanis Park Option D	
Storage Option	Above Grade Tank	Below Grade Tank	Above Grade Tank	Below Grade Tank	
Project Component					
<u>Storage Tank</u> Structure only (includes excavation, structure, deep piles, support of excavation)	\$4,000,000	\$17,500,000	\$3,370,000	\$12,100,000	
Tank Process Items (Flushing System , odor control, ventilation)	\$700,000	\$500,000	\$700,000	\$500,000	
Pump Station with Inlet/Outlet connections					
Structural	\$1,754,000	\$1,754,000	\$1,754,000	\$1,754,000	
Process	\$1,100,000	\$1,100,000	\$1,100,000	\$1,100,000	
Force main/Dewatering from DPW PS to Tank	\$631,000	\$148,000	\$2,542,000	\$1,732,000	
Diversion Chamber and Connections					
Underflow Pipe	\$685,000	\$685,000	\$685,000	\$685,000	
Diversion Chamber	\$941,000	\$941,000	\$941,000	\$941,000	
Gravity pipes in/out of New Diversion Chamber	\$525,000	\$525,000	\$525,000	\$525,000	
Construction Cost Subtotal	\$10,336,000	\$23,153,000	\$11,617,000	\$19,337,000	
Construction Contingencies (25%)	\$2,584,000	\$5,788,000	\$2,904,000	\$4,834,000	
Engineering , Legal, and Administration (30%)	\$3.101.000	\$6,946,000	\$3,485,000	\$5,801,000	
Total Project Cost*	\$16,021,000	\$35,887,000	\$18,006,000	\$29,972,000	



### Above Grade Tank at DPW Site



### Thank you for attending!



### **Extras**




### Schedule – Long Term

						2022-03-14_CSO Pilot-to-	Storage Project-P	Rev.mpp				
ID <b>(</b>	Task Name		Duration	Start	Finish	2022 12 1 2 3 4 5 6 7 8 9 101112	2023	2024	202	25	2026   2027   10  1   2   3   4   5   6   7   8   9   10  1   12   1   2   3   4   5   6   7   8   9   10  1	202
1												
2	I/I Removal Pilot Project	- No CWSRF	310 days	Mon 12/13/21	Fri 2/17/23		-					
3	Award Engineering		0 days	Mon 12/13/21	Mon 12/13/21	12/13						
4	Design Phase		136 days	Tue 12/14/21	Tue 6/21/22							
5	Bid Phase		25 days	Wed 5/18/22	Tue 6/21/22							
6	Award		0 days	Mon 6/27/22	Mon 6/27/22	6/27						
7	Construction		164 days	Tue 7/5/22	Fri 2/17/23							
8	CSO Final Compliance Pr	ogram	1443 days	Tue 3/22/22	Thu 9/30/27					•		
9	QBS Process		59 days	Tue 3/22/22	Mon 6/13/22			Prelimi	nary Bas	in		
10	Issue RFQ		0 days	Tue 3/22/22	Tue 3/22/22	3/22		D	esign			
11	RFQ's Due		0 days	Tue 5/3/22	Tue 5/3/22	5/3						
12	Interview Firms		5 days	Mon 5/23/22	Fri 5/27/22	1 C		Jar	n 2023			
13	Negotiate Fees		5 days	Mon 5/23/22	Fri 5/27/22	1 A A A A A A A A A A A A A A A A A A A						
14	Award Project		0 days	Mon 6/13/22	Mon 6/13/22	6/13						
15	Preliminary Site Inves	tigation/Geotech	210 days	Mon 6/13/22	Fri 3/31/23				Final bas	sin		
16	Preliminary Site Inv	vestigation & Geotech	164 days	Mon 6/13/22	Thu 1/26/23				dooian		Construction	
17	Final Report		0 days	Fri 1/27/23	Fri 1/27/23		1/27		desigr			
18	Storage Site - Publi	c Input Process	45 days	Mon 1/30/23	Fri 3/31/23				Oct 202	23	begins	
19	Post Pilot Project Flow	v Monitoring	153 days	Wed 3/1/23	Fri 9/29/23							
20	Flow Monitoring D	ata Collections	88 days	Wed 3/1/23	Fri 6/30/23						May 2025	
21	Flow Modeling-Cos	t-Benefit Analysis-Recommend	dation 65 days	Mon 7/3/23	Fri 9/29/23		-					
22	Storage Project - Q3 C	WSRF	1044 days	Mon 10/2/23	Thu 9/30/27					<b>/</b>		
23	Final Geo-Technica	I Investigation	100 days	Mon 10/2/23	Fri 2/16/24							
24	Storage Design		320 days		Thu 2/20/25			-				
25	Bid Phase		28 days	Thu 2/20/25	Mon 3/31/25					<b>•</b>		
26	Award		0 days	Mon 4/14/25	Mon 4/14/25					♦ 4 4	2-yr Construction	
27	Construction (to su	bstantial completion)	452 days	Sat 6/7/25	Mon 3/1/27						,	
28	Final Restoration		67 days	Tue 3/2/27	Wed 6/2/27							
29	Program Performa	nce Certification	154 days	Mon 3/1/27	Thu 9/30/27							
		Task	Pro	oject Summary	0	Manual Task	•	Start-only	E	Deadline	+	(C
Project: 2022 Date: Thu 8/2	-03-14_CSO Pilot-to-Stor 22/23			ctive Task		Duration-only		Finish-only	э	Progress		) T
June: Thur 0/2		Milestone		ctive Milestone	۵ ا	Manual Summary Rollup		External Tasks External Milestone	\$	Manual Progress	· · · · · · · · · · · · · · · · · · ·	
		ounmary	Ina Ina	cuve summary	u	Manual Summary		External Milestone	~			

28

### Federal Emergency Management Association (FEMA) Floodplain Map



### **Geotech Considerations at DPW site**

